

# Design of the China Lake NAWS Fuze Test Facility

Presenter: Ben F. Harrison, P.E.

Co-Author: Matthew Kraemer, P.E.

maintaining the data needed, and c including suggestions for reducing	lection of information is estimated to ompleting and reviewing the collect this burden, to Washington Headqu uld be aware that notwithstanding ar DMB control number.	ion of information. Send comments arters Services, Directorate for Info	regarding this burden estimate or rmation Operations and Reports	or any other aspect of the property of the contract of the con	his collection of information, Highway, Suite 1204, Arlington		
1. REPORT DATE JUL 2010	2. REPORT TYPE N/A			3. DATES COVERED			
4. TITLE AND SUBTITLE					5a. CONTRACT NUMBER		
Design of the China Lake NAWS Fuze Test Facility					5b. GRANT NUMBER		
					5c. PROGRAM ELEMENT NUMBER		
6. AUTHOR(S)					5d. PROJECT NUMBER		
					5e. TASK NUMBER		
					5f. WORK UNIT NUMBER		
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)  ABS Consulting					8. PERFORMING ORGANIZATION REPORT NUMBER		
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)					10. SPONSOR/MONITOR'S ACRONYM(S)		
					11. SPONSOR/MONITOR'S REPORT NUMBER(S)		
12. DISTRIBUTION/AVAII Approved for publ	LABILITY STATEMENT ic release, distributi	on unlimited					
	OTES 13. Department of I uly 2010, The origin	_	•	inar (34th) h	eld in Portland,		
14. ABSTRACT							
15. SUBJECT TERMS							
16. SECURITY CLASSIFIC	17. LIMITATION OF ABSTRACT	18. NUMBER OF PAGES	19a. NAME OF RESPONSIBLE PERSON				
a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified	SAR	18	RESPONSIBLE PERSON		

**Report Documentation Page** 

Form Approved OMB No. 0704-0188

## Acknowledgements

- Quality testing of Military Fuses
- Design Build Team
  - Architect: Mosher Drew Watson Ferguson



- Contractor: Soltek Pacific Construction



- Blast Design and ESQD: ABS Consulting




NAVFAC Engineering Service Center

## Background

- China Lake NAWS
  - -Ridgecrest, CA






### **Objectives**

- Design Remote Test Cells to contain effects of accidental detonation
  - Net Explosive Weight =  $10 \text{ lb}_{TNT}$
  - Minimum Standoff = 10 feet
- Personnel Protection from accidental detonation Remote Test Cell for concurrent operations:
  - Overpressure below 2.3 psi
  - Thermal flux below 0.3 cal/cm<sup>2</sup>/sec
  - Hazardous fragment energy below 58 ft\*lbf
- Determine allowable charge weight at required reduced standoffs:
  - 7 feet
  - 5 feet
  - 3 feet

# **Facility Layout**



## Fuze Test Building Work Areas


- Fuze Test Building (HD 1.1)
  - Remote Test Cells
  - Holding Cells

Test Benches and 2 gram


Centrifuge

Firing Chamber


Control Room




## **Explosives Quantities**



## **Remote Operations MCEs**




#### **Low Hazard MCEs**



#### Remote Test Cell Containment

- Design Basis
  - 10 lb<sub>TNT</sub> Containment with Directional Venting
  - Concurrent Operations of Adjacent Bays
  - Personnel Protection Category 1
  - Safety Factor of 1.2
    - Total 12 lb<sub>TNT</sub>
  - TM5-1300, 1990 Rev.




#### **Remote Test Cell Load Prediction**


- Software
  - SHOCK
  - FRANG
- Operating Heights
  - 2 feet
  - 8 feet
  - 16 feet

Design Basis Reduced Area Reduced Area Standoff **Function** Utilized 10 ft. 3 \* Slab thickness 5 ft. x 5 ft. 7 ft. 3 \* Slab thickness 5 ft. x 5 ft. 5 ft. 3 \* Slab thickness 5 ft. x 5 ft. 3 ft. 3 ft. x 3 ft. Standoff

Reduced Blast Load Area



## Remote Test Cell Predicted Response



Test Cell Response

163t Och Response							
	Response Limits		Predicted Response				
Component	Ductility	Rotation	Deflection	Ductility	Rotation	Deflection	
	(μ)	(θ)	$\Delta_{ m limit}$	(μ)	(θ)	$\Delta_{\max}$ (in)	
Side Wall	-	2 deg.	5.0 in.	-	0.4 deg.	1.0 in.	
Front Wall	-	2 deg.	2.9 in.	-	1.37 deg.	1.98 in.	
Back Wall	-	2 deg.	3.0 in.	-	0.95 deg.	1.45 in.	
Roof	-	2 deg.	5.0 in.	-	0.37 deg.	0.93 in.	
Personnel Door	10	2 deg.	0.63 in.	0.6	1.0 deg.	0.32 in.	


## Structural Design Assumptions

- Concrete strength  $-f_c' = 4,000 \text{ psi}$
- Reinforcement strength f<sub>y</sub> = 60,000 psi
- Concrete cover 2 in. on each face
- Dynamic Increase Factor (DIF)
  - Concrete Calculated based on strain rate
  - Reinforcing Steel Calculated based on strain rate
  - Personnel Door Calculated based on strain rate
- Response Criteria
  - Slabs 2 degrees rotation Category 1 response with stirrups
- Steel Blast Doors 2 degrees rotation or a ductility of 10



## **Structural Capacity**

- Structural Capacity Engineering Analysis
  - Flexural Response
  - Tension
  - Diagonal Tension Shear
  - Direct Shear
  - Factor of Safety for Design
    - 1.2 on N.E.W.



## Remote Test Cell Design Summary


- Thickness of cross-section is 20 inches, typical
- Minimum concrete compressive strength 4,000 psi
- Reinforcing
  - #5 bars, each face, each way (horizontal and vertical) at 8 inches on center
  - 2 inch concrete cover, both faces
  - #4 90-135 stirrups at 8 inches on center, each way.
  - #6 diagonal bars, no corner haunches
- The cubicle walls were securely attached at the floors and edges to adjoining slabs through development of reinforcement into the adjacent slabs. Adjacent slabs are capable of resisting the full supported moment.
- The walls must provide personnel protection from remote operations.



## Reduced Standoff Ratings

- Design Basis
   Requirements
  - Structural Response
  - Concrete Spalling
  - Scaled Distance 3
     ft/lb<sub>TNT</sub><sup>1/3</sup>

Minimum	Allowable		
Required	Charge Weight -		
Standoff	$lb_{TNT}$		
7 feet	7.5		
5 feet	3.9		
3 feet	0.8		



#### Closure

- The objectives of the design of the China Lake Fuze Test Facility included:
  - Design Remote Test Cells to contain effects of accidental detonation
    - Net Explosive Weight = 10 lb<sub>TNT</sub>
    - Minimum Standoff = 10 feet
    - Reduced Standoffs of 7 feet, 5 feet and 3 feet were evaluated
  - Personnel Protection from accidental detonation
     Remote Test Cell for concurrent operations:
    - Overpressure below 2.3 psi
    - Thermal flux below 0.3 cal/cm<sup>2</sup>/sec
    - Hazardous fragment energy below 58 ft\*lbf
- DDESB Approval Obtained and the Facility is Currently Under Construction



## Questions?

